Chapter 4: Inference and Hypothesis Testing

Statistics for Environmental Science

Mallory Barnes

Rendered October 23, 2026

This PDF was rendered on October 23, 2026. The book is updated during the semester; the latest version of this chapter is at https://malloryb.github.io/statistics_E538/04-Foundation_Inference.html.

Statistics for Environmental Science · CC BY-SA 4.0 · Credits and license: https://malloryb.github.io/statistics_E538/

Table of contents

What chance alone can produce **2**

Chance vs. not chance **5**
How rare is rare enough? . . . 6

Hypothesis tests **7**
The null and alternative hypotheses . . . 7
From simulation to a formal test . . . 7
The players . . . 8
Seeing them together . . . 9

Making the decision **13**
Terms for decision rules . . . 13
The procedure for every test . . . 16
Three equivalent ways to test H_0 . . . 16
Route 1: test statistic and critical values . . . 17
Route 2: confidence interval . . . 17
Route 3: p-value . . . 18
Reject or fail to reject . . . 21

One- and two-tailed tests **24**
One- or two-tailed: which and why? . . . 24

Chapter Summary **25**

> *Data and data sets are not objective; they are creations of human design. We give numbers their voice, draw inferences from them, and define their meaning through our interpretations.*
>
> Kate Crawford

Inferential statistics (Chapter 3) is the branch of statistics concerned with drawing conclusions about populations or causal relationships from sample data. It answers questions such as whether a manipulation caused a change, or whether a gap in infected-bat counts between two groups of caves could have arisen by random chance alone.

Chapter 3 built the sampling distribution of the sample mean and used it to estimate a confidence interval. This chapter uses the same tools to test a hypothesis, in two parts. The first part builds the logic by simulation, with no formulas. We work out what chance alone can produce, then compare a result against it. The rest of the chapter replaces the simulation with a standard hypothesis test. Once you can assume a known shape for what chance produces, such as the normal curve, you no longer have to rebuild that picture by simulation every time.

What chance alone can produce

An experiment asks whether a manipulation causes a change in what we measure. Some manipulations are so overwhelming that no statistics are required to see them. Flip a light switch up and the light comes on; flip it down and it goes off, every time. You don't need a statistical test to tell you that flipping the light switch is the cause of the change in brightness.

Few effects in environmental science behave like this. An effect is the difference a study is about, such as the change a manipulation causes in the outcome. In measurements that also contain noise, the effect is the signal. In most environmental studies, the manipulation changes the outcome *on average*, but not in every instance and not by the same amount every time.

Random chance can produce apparent differences between groups even when no real difference exists. Chapter 3 showed this with sampling. Two samples from the same distribution come out differently. The same principle applies when we compare group means. So a difference between group means is not, by itself, evidence of a real effect.

Table 1 lists the three possible explanations whenever two group means differ.

Table 1: Three possible explanations for a difference between two group means.

Explanation	What produced the difference
Real effect	The manipulation caused it.
Confound	A third variable that affects both which group a unit is in and the outcome (Chapter 2).
Sampling error	Chance. Which units happened to land in each group, including differences in variables that affect the outcome but not which group a unit is in.

Consider a scenario where we expect to find no real difference. A researcher surveys 10 caves for white-nose syndrome, a fungal disease that has killed millions of North American bats, capturing 20 bats at each cave and counting how many show visible signs of infection. Figure 1 lays out the design.

All 10 caves are drawn from the same population. There is no treatment, no environmental gradient, nothing systematic separating them, so the true infection rate is identical everywhere. In this example every cave has the same 40% infection rate, so on average 8 of the 20 bats captured at a cave show signs of infection. The counts in the figures below are simulated from that rate. We chose the 40%, and chance produced everything else. Splitting the 10 caves into two groups of 5 is arbitrary. Any difference we see between those groups therefore *has* to be sampling error, so this scenario shows what chance alone can produce.

Figure 2 shows one run of this scenario: the mean number of infected bats in each group.




Figure 1: The bat-cave scenario study design. The split into two groups is arbitrary, so there is no real difference for the test to find.




Figure 2: Mean number of infected bats per site for two groups drawn from the same population. Note the zoomed y-axis, which does not start at 0.

Group A and Group B have different mean counts, 8.4 and 9.0 infected bats. Both groups were drawn from the same population of caves, with the same infection risk, so the gap is sampling error.

We need a way to tell whether an observed difference is real or the result of chance.

Chapter 2 built a chance window for correlations by repeating a random draw 1,000 times. We can build one for group means the same way, by running the same arbitrary split many times and recording each result. The **mean difference** is the mean count for Group A minus the mean count for Group B. We summarize each run with this one number. One replication is one complete rerun of the survey. It samples all 10 caves from the same population, splits them 5 and 5, and computes the two group means. Figure 3 shows the mean differences for 10 replications.




Figure 3: Difference in mean infected count between Group A and Group B across 10 replications. The true difference is zero, but sampling error produces a non-zero difference in almost every replication.

A bar at zero means the two groups had the same mean count in that replication. Positive values indicate Group A was higher; negative values indicate Group B was higher. Chance produces a new difference every time, but across these 10 replications no difference was larger than 1.8 bats in either direction. To see which sizes are common and which are rare, we run 10,000 replications and plot the mean differences as a histogram.

Before you look. Each replication gives one mean difference, the Group A mean minus the Group B mean. The height of a bar in Figure 4 counts how many of the 10,000 replications produced a difference of that size. Decide where you expect the tallest bar to be, and how far from zero you expect the differences to reach.

Most replications produced a difference near zero, so the tallest bar is the one at zero. Larger differences in either direction occur less and less frequently, and differences beyond about ± 3 are possible, but only 2.6% of the 10,000 replications produced one. The chance window for a study design is the distribution of results that chance alone produces when the study is repeated many times with no real effect (Chapter 2). This histogram is the chance window for this study design.

We can use this window to evaluate any observed difference. If a study found a difference of 1 infected bat between two groups, that falls well inside the range of differences chance produced, because 52% of the 10,000 replications produced a difference at least that large. If the study found a difference of 6 bats, that would fall outside the window. Chance never produced a difference that large in 10,000 replications. When




Figure 4: Histogram of mean count differences between Group A and Group B over 10,000 replications. All differences arise from chance alone. The most frequent difference is near zero; larger differences occur less often. Differences beyond about ±3 are rare. The blue dot-dash curve is a normal curve with mean 0 and standard deviation 1.39.

an observed result almost never happens by chance, we have grounds to conclude that *something other than chance* produced it.

> **i** Note: Which direction?
>
> **Still probability, model → data.** The chance window starts from a world we chose, every cave at the same infection rate, and shows the differences that world produces. The 1-bat and 6-bat results above are hypothetical, used to show what the window can tell us. No real study's data have entered yet.

Chance vs. not chance

Where to draw the line between "chance could have" and "chance didn't" is a judgment call. The window tells us what chance can do, but it does not tell us where that line goes.

Figure 5 draws lines on the same bat histogram from above. The boundaries are the smallest and largest differences chance actually produced across the 10,000 replications.

Across the 10,000 replications, chance produced differences from about -5.6 to 5.4 bats.

- **Chance (gray).** Chance produced differences like this routinely, so there is no reason for suspicion.
- **Ambiguous (gold).** The gold zones are the edges of what chance produced. Chance *can* produce differences this large, but rarely, so chance is unlikely here but not ruled out.
- **Not chance (red).** Chance never produced a difference this large in 10,000 replications, which gives grounds to suspect something beyond sampling error.




Figure 5: Decision boundaries applied to the histogram of mean count differences from Figure 4. Gray marks the range chance did produce across 10,000 replications; gold marks the edges of that range, which chance reached only rarely; red marks the differences chance never produced at all.

How rare is rare enough?

Environmental scientists already describe rarity with the **100-year flood**. A 100-year flood is a flood with about a 1-in-100 chance of happening in any given year. It does not arrive once a century on a schedule. Table 2 follows that chance over a 30-year mortgage and sets it beside a much rarer flood, one with a 1-in-10,000 annual chance. The second column is $1 - (1 - \text{annual chance})^{30}$, the chance that at least one of the 30 years has the flood.

Table 2: Chance of at least one flood over a 30-year mortgage, for two annual flood risks.

Annual chance	Chance of at least one in 30 years
1 in 100 (1%)	26%
1 in 10,000 (0.01%)	0.3%

A 1% annual chance adds up to roughly a 26% chance of at least one such flood over the mortgage. A 1-in-10,000 annual risk stays under 0.3% over the same 30 years.

Rare events still happen. A difference in the gold zone of Figure 5 can also occur by chance, and how rare it is changes what we are willing to conclude from it.

Where the gold zone ends is a judgment call. A stricter line means fewer false alarms, where we conclude there is an effect when there is none, and more missed real effects. A looser line means the reverse. Researchers standardize that call with a convention, $\alpha = 0.05$, defined later in this chapter. It is 1 in 20. Because 5% of 10,000 is 500, the most extreme 500 of the 10,000 replications would count as rare enough. That line is far looser than the red zone, which contains only differences chance never produced.

Hypothesis tests

The null and alternative hypotheses

The chance window described a world where nothing but chance is at work. A formal test gives that world a name.

Comparing two groups needs the tests in Chapter 6. From here on we compare a single sample against a specific value, such as a regulatory limit or a historical average. Later in this chapter, for example, a county compares its average daily PM2.5 with its target of 12 µg/m³.

The null hypothesis, H_0, is the claim of no effect or no difference. In this chapter's tests, it says the population mean equals a reference value, written μ_0, such as a target or the value with no manipulation. If H_0 is true, any gap between the sample mean $\bar{x}$ and μ_0 is sampling error.

The alternative hypothesis, H_a, is the claim that the population mean does not equal μ_0. It can also point in one direction only, larger or smaller. Section covers when that is justified.

$$H_0 : \ \mu = \mu_0 \qquad H_a : \ \mu \neq \mu_0$$

In the bat example, H_0 would say the two groups of caves have the same population mean, $\mu_A = \mu_B$.

Null value notation. In this chapter, hypotheses are about the population mean μ, compared with the constant μ_0. The sample mean $\bar{x}$ is never part of H_0 or H_a. It is the evidence we bring to test them.

From simulation to a formal test

Everything so far was built by simulation: 10,000 replications, plotted as a histogram, with hypothetical results compared against it. Chapter 3 already supplies a shortcut that saves rebuilding a chance window for every question. Sample means have a predictable distribution of their own. At every sample size it is centered on the population mean, with spread $\sigma/\sqrt{n}$. The central limit theorem adds that it is close to normal once the sample is large enough. That lets us replace the simulated chance window with a curve whose shape we already know.

We can check the shortcut on the bat histogram. The blue dot-dash curve drawn over it in Figure 4 is a normal curve with mean 0 and standard deviation 1.39, worked out from the 40% infection rate and the 5 caves per group. One cave's count is 20 bats at a 40% infection rate, and its standard deviation comes from the formula for the standard deviation of a binomial count, which this chapter uses only here. The histogram shows a difference between two 5-cave group means.

$$\begin{aligned} \text{One cave's SD} &= \sqrt{20 \times 0.4 \times 0.6} = \sqrt{4.8} = 2.19 \\ \text{SE of a 5-cave mean} &= 2.19/\sqrt{5} = 0.98 \\ \text{SD of the difference} &= \sqrt{0.98^2 + 0.98^2} = 1.39 \end{aligned}$$

Chapter 6 gives the general formula for the spread of a difference between two means. The curve follows the 10,000 simulated differences closely, so it could have replaced the simulation.

Table 3 lines up each piece of the simulation with the piece of the formal test that replaces it.

Table 4: The players in a hypothesis test, and the line each is drawn with in this chapter's figures.

	Line	Player	What it is
If H_0 were true		μ_0	The population mean if H
If H_0 were true		Null population distribution	The population if H_0 were
If H_0 were true		Sampling distribution of the sample mean under H_0	How $\bar{x}$ would vary across r
From the sample		$\bar{x}$	The sample mean: the one
From the sample		Estimated population distribution	Centered at $\bar{x}$, with the sa
From the sample		Sampling distribution of the sample mean	Our estimate of how samp
From the sample		Confidence interval	$\bar{x} \pm 1.96$ standard errors, b
The truth		True population distribution	The population the data a

Table 3: The simulated chance window and the formal test it turns into.

Idea	Simulation (bat example)	Formal test
What chance alone produces	Histogram of 10,000 mean differences (Figure 4)	Sampling distribution of the sample mean under H_0
Where the line is drawn	Gold and red edges, set by eye	Critical values, set by α
How rare our result is	Count of replications at least as extreme (0 of 10,000 for a 6-bat difference)	p-value
Verdict	Inside or outside the window	Reject or fail to reject H_0

The bat histogram shows differences between two group means, and the formal test in this chapter uses a single sample mean. In both, an observed result is compared with what chance alone produces under H_0.

The normal-curve shortcut works only when the sampling distribution of the sample mean is close to normal. A test uses that sampling distribution, and the population itself does not have to be normal. That distribution is close to normal once the sample is large enough, whatever the population's shape (the central limit theorem). With a small sample, it is normal only if the population is roughly normal. The first check is the sample's histogram, which should show no strong skew and no extreme outliers, and Chapter 6 adds more. When the checks fail, the nonparametric tests in Chapter 7 take over.

The players

A test is about μ, the true population mean, which we never observe. Everything we know about it comes from one sample. The null hypothesis proposes a value for it, μ_0. We reject H_0 only if the sample mean, $\bar{x}$, is farther from μ_0 than sampling error would plausibly produce if the null were true.

Several distributions and values take part in that comparison. Table 4 lists every one, with the line each is drawn with in this chapter's figures. They fall into three groups: what we would expect if H_0 were true, what the sample gives us, and the truth we never see.

Seeing them together

The figures below draw the players a curve or two at a time.

The population curves in these figures are drawn as normal for clarity. As explained above, a test does not need them to be.

Notation reminder. Chapter 3 wrote a normal curve as $X \sim \text{Normal}(\mu, \sigma)$, with the standard deviation second. From here on we use the more common shorthand $X \sim N(\mu, \sigma^2)$, read "the random variable X is normally distributed with mean μ and variance σ^2." A normal curve needs just those two numbers, a center and a spread. In this shorthand the second number is the variance, the square of the standard deviation. A population with mean 12 and standard deviation 6, for example, is $N(12, 36)$.

1. The null population distribution.

The **null population distribution** is the population we would have if H_0 were true. Its center, μ_0, comes from H_0 itself, and Figure 6 draws it as a blue curve centered on the magenta line at μ_0. Its spread is the population standard deviation, σ. In practice σ is almost never known, and analyses use the sample's standard deviation, s, in its place. This chapter treats σ as known to keep the first test simple. A known σ with an unknown μ does happen, for example when years of daily readings from one air monitor show how much its readings vary and the question is whether this year's mean has shifted. Chapter 6's t-tests adjust for using s instead of σ.




Figure 6: Null population distribution: the population we would have if H_0 were true, centered at μ_0.

2. Null vs. true population.

In an idealized world where H_0 is exactly true, the true population and the null population distribution are identical. In Figure 7 the blue null curve is drawn on top of the orange true population curve, so the two make a single bell shape. The **true population distribution** is the population the data actually came from. In reality, we never know it. H_a is a claim about this true population distribution, about where its mean might be.

> **i** Note: Which direction?
>
> **The switch to statistics, data → model.** Steps 1 and 2 came from H_0, a model we proposed. Step 3 starts from the sample we actually have and works back toward the population it came from.

3. The sample's picture of the truth. We never see the true population, but we do have a sample. The **estimated population distribution** is a normal curve centered at the sample mean, $\bar{x}$, with the sample's standard deviation, s, as its spread. It is our best picture of the true population. With a representative sample, the two line up closely, as the light-green dashed and orange curves do in Figure 8.




Figure 7: True population distribution equals the null population distribution (H_0 true): $\mu = \mu_0$.




Figure 8: A representative sample: the estimated population distribution, built from the sample, lines up closely with the true population distribution.

4. From individual readings to sample means. By the central limit theorem, the sampling distribution of the sample mean is close to a normal curve once the sample is large enough, so it needs only a center and a spread. This curve is our estimate of the Chapter 3 sampling distribution. That distribution is centered at μ, which we do not know, so the estimate is centered at $\bar{x}$, the same as the estimated population. Its spread is the standard error, the population standard deviation divided by $\sqrt{n}$ (Chapter 3). With real data we use the sample's standard deviation, s, so the standard error is $s/\sqrt{n}$. The divisor is $\sqrt{n}$, not $\sqrt{n-1}$, because the $n-1$ already went into computing s in Chapter 3. This chapter treats σ as known, so the standard error here is $SE_{\bar{x}} = \sigma/\sqrt{n}$. In the shorthand, it is $N(\bar{x}, SE_{\bar{x}}^2)$, with a much smaller spread than the estimated population.

Figure 9 then makes the population right-skewed while keeping its standard deviation. The skew leaves the spread of the sampling distribution unchanged at every n, because that spread is still the standard deviation divided by $\sqrt{n}$. Only the normal shape depends on the central limit theorem, and it needs a large enough sample.




Figure 9: From individual readings to sample means. The sampling distribution of the sample mean (dark-green dot-dash) shares the estimated population's center, $\bar{x}$, with the standard error as its spread. When the population turns right-skewed with the same standard deviation, the sampling distribution keeps the same spread, and once the sample is large enough it keeps its normal shape as well. (Final frame. The animated version is in the web edition of this book.)

5. From the null population to sample means. The **sampling distribution of the sample mean under** H_0 describes how $\bar{x}$ would vary across many samples if H_0 were true. It is $N(\mu_0, SE_{\bar{x}}^2)$, centered at μ_0. Its spread is again the standard error, the null population's standard deviation divided by $\sqrt{n}$. With σ treated as known, this is the same standard error as in step 4. Figure 10 draws it as a blue dot-dash curve. The null population distribution shows how single readings would vary if H_0 were true. The sampling distribution under H_0 shows how sample means would vary, so it is narrower by a factor of $\sqrt{n}$. It is the formal version of the chance window in Figure 4. The critical values later in the chapter come from it.




Figure 10: From the null population to sample means: the null population distribution (blue solid) and the sampling distribution of the sample mean under H_0 (blue dot-dash) share a center, μ_0. Dividing the spread by $\sqrt{n}$ makes the second much narrower.

All of them at once. With every player on one set of axes the picture is crowded, so the rest of the book shows only the pieces a given question needs. Figure 11 adds them one at a time, grouped as in Table 4, and ends with all of them together.




Figure 11: The players, added one at a time: first everything built from H_0, then everything built from the sample, then the true population, ending with all of them on one set of axes. (Final frame. The animated version is in the web edition of this book.)

The two curves a decision uses. Figure 12 shows only the two sampling distributions of the sample mean. The two curves have the same spread, the standard error, and different centers. The one under H_0 is centered at μ_0 and shows how $\bar{x}$ would vary if H_0 were true. The one from the sample is centered at $\bar{x}$ and shows how sample means vary around our best guess for μ. The critical values and the p-value come from the first, and the confidence interval comes from the second.

Making the decision

Terms for decision rules

Four terms guide the decision in a hypothesis test. The first is the quantity every test computes.

Test statistic. A test statistic is the effect you observed divided by how much it varies by chance. The observed effect is the distance between what you measured and what H_0 predicted. It contains any true effect plus sampling error. The error is how much that distance varies by chance alone (in later chapters, an estimate of it):




Figure 12: The two curves a decision uses: the sampling distribution of the sample mean under H_0 (blue dot-dash), centered at μ_0, and the sampling distribution of the sample mean from the sample (dark-green dot-dash), centered at $\bar{x}$. Both have the standard error as their spread.

$$\text{statistic} = \frac{\text{effect}}{\text{error}}$$

Term	In this chapter
effect	$\bar{x} - \mu_0$, the distance between the sample mean and the value H_0 proposes
error	$SE_{\bar{x}} = \sigma/\sqrt{n}$, how far sample means move around by chance alone

Put together, this chapter's test statistic is z:

$$z = \frac{\bar{x} - \mu_0}{\sigma/\sqrt{n}}$$

Whether a sample mean 2 units from μ_0 is far from it depends on how much difference chance produces for a study with that sample size. The chance window measured exactly that earlier in this chapter. The test statistic writes that comparison as a single number, the number of standard errors the effect spans. The t and F tests later in the book are versions of the same ratio.

How the z statistic relates to Chapter 3's z-score.

Chapter 3: z-score for one value	This chapter: z statistic for a sample mean
$z = \dfrac{x - \mu}{\sigma}$	$z = \dfrac{\bar{x} - \mu_0}{\sigma/\sqrt{n}}$
How many SDs one value is from the population mean	How many SEs the sample mean is from μ_0

Both divide a distance by a spread, but the spread comes from a different distribution. A z-score places one value on the population distribution, where the spread is σ. A z statistic places $\bar{x}$ on the sampling distribution of the sample mean under H_0, which is narrower, so the spread is $SE = \sigma/\sqrt{n}$. Do not divide $\bar{x} - \mu_0$ by σ instead of SE. That uses the wide curve to answer a question about the narrow one, and it makes the statistic $\sqrt{n}$ times too small.

A large statistic means the effect is big compared to the noise, and a small one means it is not. The rest of this section sets where to draw the line between a large statistic and a small one.

Significance level (α). α is the probability of rejecting H_0 given that H_0 is true, and we choose it *before* the test. It is a conditional probability, $P(\text{reject } H_0 \mid H_0 \text{ true})$. Rejecting a true H_0 is called a Type I error, and Chapter 5 covers error types. A common choice is $\alpha = 0.05$. Smaller α means a test needs a larger test statistic before it rejects H_0. It also produces wider confidence intervals, because the confidence level is $1 - \alpha$ (defined below). At $\alpha = 0.01$, for example, the two-tailed critical value is 2.58 instead of 1.96, and the 99% interval is $\bar{x} \pm 2.58$ standard errors.

***p*-value.** A p-value is the probability, assuming H_0 is true, of obtaining a test statistic at least as extreme as the one we observed. At least as extreme means at least as many standard errors from μ_0, counting both directions in a two-tailed test. Small p means our data look unusual under H_0.

Confidence level. Confidence level is the proportion of confidence intervals that would contain the true parameter if we repeated the study many times, collecting new data and building a new interval each time.

$$\text{Confidence Level} = 1 - \alpha$$

With $\alpha = 0.05$, about 95% of intervals constructed this way will capture the true value. Chapter 3's warning still applies, because the 95% describes the procedure and any one interval either contains μ or misses it.

The procedure for every test

Every test in this book follows the same steps. Table 5 lists them, and the test cards in later chapters fill in steps 4 and 5 for each test.

Table 5: The procedure for every hypothesis test.

Step	What you do	Uses the data?
1	State H_0 and H_a, including whether the test is one- or two-tailed	No
2	Choose α	No
3	Choose the test and check its assumptions	The checks do, but not the test result
4	Find the critical value(s) from α, the tails, and the test's null distribution	Depends on the test. The z-test does not
5	Calculate the test statistic	Yes
6	Compare the statistic with the critical value(s). Reject H_0 if it falls in the rejection region, otherwise fail to reject	Uses step 5
7	Report the effect with its 95% CI, the test statistic, and p	Uses step 5

For the z-test, step 4 needs nothing from the data. The critical values are the standard normal cutoffs from Chapter 3. The 68-95-99.7 rule puts about 95% of a normal distribution within 2 standard deviations of its center, and the exact cutoff is 1.96, so at $\alpha = 0.05$, two-tailed, the critical values are ± 1.96 for every z-test. Later tests look up their critical values the same way, from the t, F or χ^2 distribution with the df the design gives.

Software reports p instead of critical values. Comparing p with α replaces steps 4 and 6 and gives the same decision, as Route 3 below shows.

Three equivalent ways to test H_0

All three routes use the same two numbers, the distance $\bar{x} - \mu_0$ and the standard error.

1. **Test statistic / critical values.** A **critical value** is the value of the test statistic that cuts off the most extreme α of the sampling distribution under H_0. The **rejection region** is the set of test-statistic values beyond the critical value(s). Choose α, find the critical value(s), and compute your observed statistic. Reject H_0 if the statistic falls in the rejection region.
2. **Confidence interval (two-sided).** Build a $(1-\alpha)$ CI for the parameter. Reject H_0 if μ_0 lies outside the CI, and fail to reject if it lies inside.
3. **p-value.** Compute the p-value for your observed statistic under H_0 and compare to α. Reject H_0 if $p < \alpha$.

The numbers in this example are invented. A county averages daily PM2.5 over $n = 36$ days and gets $\bar{x} = 14.1$ µg/m³. The county's target is $\mu_0 = 12$, and $\sigma = 6$ is treated as known. The code below works out what each route needs, with `qnorm()` for the critical value and `pnorm()` for the p-value.

```
xbar_pm <- 14.1; mu0_pm <- 12; sigma_pm <- 6; n_pm <- 36
se_pm <- sigma_pm / sqrt(n_pm)          # standard error
z_pm  <- (xbar_pm - mu0_pm) / se_pm     # test statistic
crit_pm <- qnorm(0.975)                 # two-tailed critical value at alpha = 0.05
ci_pm <- xbar_pm + c(-1, 1) * crit_pm * se_pm   # 95% CI
p_pm  <- 2 * pnorm(-abs(z_pm))          # two-tailed p-value
```

Table 6 runs this one example through all three routes. Each route reaches the same decision, reject H_0.

Table 6: One invented PM2.5 example run through all three routes, at $\alpha = 0.05$.

Route	Computation	Result	Decision
Critical value	$SE = 6/\sqrt{36} = 1.0$, $z = (14.1 - 12)/1.0 = 2.10$	$2.10 > 1.96$	Reject
Confidence interval	$14.1 \pm 1.96 \times 1.0$	95% CI [12.14, 16.06]	12 is outside, so reject
p-value	`2 * pnorm(-2.10)`	$p = 0.036$	$0.036 < 0.05$, so reject

The critical-value route gives only a decision at α, reject. The confidence interval adds the range of values of μ consistent with the data, [12.14, 16.06] µg/m^3, and the p-value adds an exact measure of how unusual the data are under H_0, $p = 0.036$.

Route 1: test statistic and critical values

Critical values come from the sampling distribution of the sample mean under H_0, built in Figure 10.

Figure 13 draws it for the PM2.5 example, a two-tailed test at $\alpha = 0.05$, marked off in standard errors from μ_0. The red lines are the critical values, 1.96 standard errors on either side of μ_0. The value 1.96 is `qnorm(0.975)`, the 97.5th percentile of the standard normal, which leaves 2.5% in the upper tail (Chapter 3). They cut off the most extreme 5% of the curve, 2.5% in each tail, and those shaded tails are the rejection regions. The county's $\bar{x} = 14.1$ is 2.10 standard errors above $\mu_0 = 12$, inside the right-hand rejection region. Counting that distance in standard errors is exactly the test statistic from Table 6, $z = (\bar{x} - \mu_0)/SE = 2.10$.

Decision rule:

- If the observed test statistic falls in the non-rejection region, between the critical values, we fail to reject H_0 because the result is consistent with chance variation.
- If it falls in either rejection region, we reject H_0 because the result is too extreme to attribute to chance alone at the 5% level.

α is the red area in Figure 13. The p-value (Route 3) is the area beyond the observed statistic, in both tails. Because $\bar{x}$ is inside a red tail, the area beyond it is smaller than the red area. Here $p = 0.036$, below $\alpha = 0.05$.

Route 2: confidence interval

The confidence-interval route makes the same decision using the sampling distribution of the sample mean from the sample. The rejection region and the confidence interval both reach 1.96 standard errors from their centers, and their centers differ. The rejection region is centered at μ_0 and asks whether $\bar{x}$ is too far from it. The confidence interval is centered at $\bar{x}$ and asks whether μ_0 is too far from it. The distance between $\bar{x}$ and μ_0 is the same from either end, so for a two-tailed test the two routes always reach the same decision. The confidence-interval route never uses the null population distribution, only the single value μ_0.




Figure 13: Two-tailed test at $\alpha = 0.05$: the sampling distribution of the sample mean under H_0 (blue dot-dash), centered at μ_0 (magenta) and marked off in standard errors. Red lines are the critical values at ± 1.96 SE. The shaded tails are the rejection regions. The PM2.5 example's $\bar{x}$ (dotted) falls 2.10 SE above μ_0, in the rejection region.

Start from the sampling distribution of the sample mean from the sample, built in Figure 9: centered at $\bar{x}$, with the standard error as its spread. A sample mean falls within 1.96 standard errors of the true mean μ about 95% of the time. Whenever $\bar{x}$ is within 1.96 standard errors of μ, μ is also within 1.96 standard errors of $\bar{x}$. So the interval $\bar{x} \pm 1.96\,SE$, the middle 95% of this curve, captures μ in about 95% of samples. This interval is the 95% confidence interval. It contains the values of μ that are consistent with our sample (Figure 14). For the PM2.5 example the interval is 95% CI [12.14, 16.06] µg/m³. Then ask where μ_0 falls (Figure 15).

Decision rule:

- If μ_0 lies inside the CI bar, we fail to reject H_0.
- If μ_0 lies outside the CI bar, we reject H_0 at $\alpha = 0.05$.

In the right panel, the target of 12 µg/m³ is only 2.1 µg/m³ from $\bar{x}$, about 0.35 population standard deviations, so a single day at 12 µg/m³ would be unremarkable. It is not a plausible value for the *mean*, because sample means vary less than individual readings do. Measured in standard errors, the same distance is 2.10, beyond the 1.96 that bounds the 95% interval.

For the z test in this chapter, a two-tailed test of $H_0 : \mu = \mu_0$ at level α reaches the same decision as checking whether μ_0 lies inside the $100(1-\alpha)\%$ confidence interval. At $\alpha = 0.05$, that is the 95% interval. The CI shows both the decision (reject or not) *and* the range of parameter values still consistent with the data.

Route 3: *p*-value

The p-value is an area under the curve, so it comes from `pnorm()`, which Chapter 3 introduced as the area to the left of a value. For the PM2.5 example's $z = 2.10$ in Figure 16, `pnorm(-2.10)` gives the area below -2.10, about 0.018, which by symmetry equals the area above $+2.10$. A two-tailed test counts both tails, so $p =$ `2 * pnorm(-2.10)` ≈ 0.036. Reject if $p < \alpha$. Here $0.036 < 0.05$, so we reject.




Figure 14: The 95% confidence interval: the middle 95% of the sampling distribution of the sample mean from the sample, $\bar{x} \pm 1.96$ standard errors.




Figure 15: The decision for the PM2.5 sample, the same in both panels. Left: a target of $\mu_0 = 13$ (magenta) would fall inside the 95% confidence interval, so we would fail to reject H_0. Right: the county's target, $\mu_0 = 12$, falls outside it, so we reject H_0.




Figure 16: p-value lens: the two-tailed p-value is the gray area beyond the observed statistic (dotted line), in both tails, under the null. Red lines mark the critical values.

A p-value is a conditional probability. Chapter 3 introduced conditional probability and its notation, $P(A \mid B)$, which puts the event you are asking about to the left of the bar and the condition you already know to the right. A p-value has exactly that form:

$$p = P(\text{a statistic at least this extreme} \mid H_0 \text{ is true})$$

To the right of the bar is what you have assumed, that H_0 is true. To the left are the data.

Flipping the bar gives a different probability. In Chapter 3's stream example, flipping the two sides of the bar turned $P(\text{exceed} \mid \text{heavy rain}) = 0.60$ into $P(\text{heavy rain} \mid \text{exceed}) = 0.30$. Here, it is tempting to read $p = 0.036$ as "a 3.6% chance the null is true." That is a different conditional probability, and a test cannot give it to you:

Probability	What it means	Does a test give it?
$P(\text{data this extreme} \mid H_0 \text{ true})$	How often chance alone produces data like yours, if H_0 holds	Yes, this is the p-value
$P(H_0 \text{ true} \mid \text{data})$	How likely the null is, given what you observed	No

A p-value keeps H_0 to the right of the bar, the way $P(\text{exceed} \mid \text{heavy rain})$ keeps heavy rain there. The test assumes H_0 and asks how unusual the data would be under it. In this book, H_0 is treated as a fixed fact about the population, either true or false. A fixed fact has no probability attached to it, so the test cannot report one for H_0. In the PM2.5 example, $p \approx 0.036$ means that if H_0 were true, a statistic at least 2.10 standard errors from μ_0 in either direction would turn up about 3.6% of the time. It does not mean there is a 3.6% chance that H_0 is true.

Reject or fail to reject

Test outcomes are binary: we either reject H_0 or fail to reject H_0. Failing to reject means this design did not separate the effect from chance, and the data are consistent with H_0. It never means the effect is zero, so we never *accept* H_0. Sampling variability means we can't prove H_0 is true. Similarly, we don't formally *accept* H_a, but we can say the results provide support for H_a when H_0 is rejected.

Report the exact p and the confidence interval. For the PM2.5 example, that is $p = 0.036$ and 95% CI [12.14, 16.06] µg/m³. Chapter 5 adds effect size to this list.

The two figures below use invented samples, one far from μ_0 and one close to it, to show each outcome of a two-tailed test.

1. **Reject the null hypothesis (two-tailed test).** The sample mean falls beyond the critical values, in the rejection region. The confidence interval also excludes the null mean. In Figure 17, $\bar{x}$ is 3.75 standard errors from μ_0 ($z = -3.75$), well past the critical values of ± 1.96, and the two-tailed p-value is below 0.001, far below $\alpha = 0.05$. All three routes say reject.
2. **Fail to reject the null hypothesis (two-tailed test).** The sample mean falls in the non-rejection region, and the confidence interval includes the null mean. Here $\bar{x}$ is 1 standard error from μ_0 ($z = -1.00$), inside the critical values, and the two-tailed p-value is 0.32, above $\alpha = 0.05$. All three routes say the evidence is consistent with chance variation, so we fail to reject H_0.

> Warning: A significant result does not say what caused it
>
> Every hypothesis test in this book asks one question, whether chance alone could have produced this result. Other methods start from two or more candidate explanations, say a steady linear decline




Figure 17: Two-tailed test, reject H_0. Blue: the sampling distribution of the sample mean under H_0, with its rejection regions shaded beyond ± 1.96 SE. $\bar{x}$ falls in one. Green: the sampling distribution of the sample mean from the sample, with its 95% confidence interval. μ_0 falls outside it.




Figure 18: Two-tailed test, fail to reject H_0. $\bar{x}$ is 1 standard error from μ_0, inside the critical values of ± 1.96 SE, and the confidence interval from the sample includes μ_0.

versus a sharp threshold response, and ask which one the data support better.
Rejecting chance as the explanation tells you that *something* is going on, but not always *what*.

Table 7 collects the one-sample z-test on one card.

Table 7: Test card: one-sample z-test.

Purpose	Compare a sample mean to a reference value μ_0 when the population SD σ is known For example, σ from a long monitoring record
Hypotheses	$H_0 : \mu = \mu_0$ $H_a : \mu \neq \mu_0$
Assumptions	σ known Sampling distribution of the sample mean approximately normal (a normal population, or n large enough, Chapter 3) |
Test statistic	$z = (\bar{x} - \mu_0)/(\sigma/\sqrt{n})$ Critical values ± 1.96 at $\alpha = 0.05$ (two-tailed) Known before collecting data, from the standard normal (about 2 by the 68-95-99.7 rule)
Report	$\bar{x}$ and 95% CI z and n p

One- and two-tailed tests

H_a says where the true population mean could be if it does not equal μ_0. A two-tailed alternative says it might be below μ_0 or above it. A one-tailed alternative says it can only be on one side (Figure 19).




Figure 19: What H_a claims. The null population distribution (blue) is centered at μ_0. The orange curves are possible true population distributions under H_a: on either side for a two-tailed alternative (left), on one side only for a one-tailed alternative (middle and right).

The test builds in those claims by where it places α. A two-tailed test splits α between both tails of the sampling distribution of the sample mean under H_0. A one-tailed test puts all of α in the one tail H_a points toward (Figure 20).

One- or two-tailed: which and why?

Use this rule of thumb:




Figure 20: Where α goes. Both panels show the sampling distribution of the sample mean under H_0 (blue dot-dash), in standard-error units. Left, two-tailed ($H_a: \mu \neq \mu_0$): $\alpha/2$ in each tail, critical values at ± 1.96. Right, one-tailed ($H_a: \mu > \mu_0$): all of α in the right tail, critical value at 1.645.

- Two-tailed (default): You care whether μ differs from μ_0 in either direction.
- One-tailed (only if justified): Differences in the opposite direction are scientifically irrelevant and would not change your decision or action.

Chapter 5 turns the second bullet, whether a result in the other direction would change your action, into a question you can answer before collecting data.

At $\alpha = 0.05$, a one-tailed test's critical value is 1.645 instead of 1.96, so it *rejects on less evidence, but only in the direction you named in advance.* If the effect goes the other way, a one-tailed test cannot detect it at all, however large it is. Most studies should not give that up, because a result in the unexpected direction is often the most useful thing a study finds.

Choose the direction before you see the data. Picking the tail afterward, because it gives the smaller p-value, makes your actual chance of a Type I error, rejecting a true H_0, higher than the α you report.

Chapter Summary

Why it matters. This chapter connects describing data to drawing conclusions from it. Every test after this point follows the same steps: work out what chance alone could produce, then ask whether your result is rare enough under chance, by a standard set in advance (α), to reject chance as the explanation.

Core ideas

- **Chance produces differences on its own.** Split one population into two arbitrary groups and their means will differ anyway, from sampling error alone. The question to ask is whether the difference is bigger than chance can account for.
- **You can build the chance window.** The chance window is the distribution of results that chance alone produces when a study with no real effect is repeated many times. Simulating thousands of replications shows what chance can produce for a study with that design and sample size.
- **Rarity is a judgment, and it needs a convention.** The 100-year flood uses the same reasoning outside statistics. A 1% annual chance is small, but over a 30-year mortgage it adds up to about a 26% chance. $\alpha = 0.05$ standardizes that judgment so researchers do not each draw their own line.

- **A hypothesis test is the practical shortcut.** Once you can assume the sampling distribution of the sample mean under H_0 is normal, the simulated chance window becomes a curve and the decision becomes a calculation, with the same logic as the simulation.
- **One pair of curves comes from the sample and one from H_0.** From the sample: the estimated population distribution and the sampling distribution of the sample mean from the sample, which gives the confidence interval. Under H_0: the null population distribution and the sampling distribution of the sample mean under H_0, which gives the critical values and p-value. The true population distribution is never known.
- **Three routes give the same decision.** A test statistic against a critical value, a confidence interval, and a p-value are three ways of asking the same question. For the two-tailed z test at the same α, they always agree.
- **Commit to one- or two-tailed in advance.** Default to two-tailed. Choosing after seeing the data raises your actual error rate above the α you claimed.